

## KANNUR UNIVERSITY

Planning & Development Branch

### NOTICE INVITING TENDERS

No. PLD/C1/2511/NAAC VISIT 2021/TVKRA/KNRUTY/21

Dated --/12/2022

Sealed competitive Tenders are invited from registered Contractors for the Supply and Installation of Street Lights and Electrical Works at the Palayad Campus, Kannur University.

Sl.No.	Name of work	EMD	Time for completing the work	Last date of submission
1	Supply and installation of Street Lights and Electrical Works at the Palayad Campus, Kannur University.	₹ 9225/-	45 days	31-12-2022 3.00pm

#### Conditions

1. Tender form can be had from Kannur University website [www.kannuruniversity.ac.in](http://www.kannuruniversity.ac.in).
2. Cost of tender form is **Rs.750/- + (18%) GST** to be remitted separately as DD drawn in favour of The Finance Officer, Kannur University.
3. The tender, tender form and an initial agreement executed and signed in Kerala stamp Paper of value **Rs.200/-** should be sent to the University before the due date.
4. The successful tenderer should deposit a sum equivalent to **5%** of the value of the contract as Security Deposit before signing the agreement within the period specified in the letter of acceptance of the tender.
5. The rate should be inclusive of all taxes and nothing extra shall be admissible over and above the rate quoted.
6. The payment will be made through account payee cheque and no advance payment will be sanctioned.
7. Received tenders will be opened on **31/12/2022 at 3.30pm**.

The Details of work can be had from the Engineering wing, Thavakkara, Kannur University on all working days up to 5.00pm.

The Registrar, Kannur University reserves the right to reject any of the tenders or all the tenders without assigning any reason whatsoever.

To

1. The Notice board
2. Website

Registrar(i/c)

**KANNUR UNIVERSITY**

**TENDER SCHEDULE**

**NAME OF THE WORK: STREET LIGHT & ELECTRICAL WORKS AT PALAYAD CAMPUS**

**PID/C1/2511/NAAC-VISIT-2021/TVKRA/KNRUTY/21**

**Last date of submission.....**

Sl.No	Item Description	Unit	Quantity	Rate in Figures	Rate in Words	Amount
1.	Supply & laying of one number PVC insulated and PVC sheathed armoured aluminium power cable of 1.1KV grade of the following sizes in the existing RCC/ HUME / STONE WARE/ GI/ DWC pipe as required. 3 core 10 sq mm	Mtr	550			
2	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface /recessed steel/PVC conduit as required 2 x 1.5 sq.mm	Mtr	80			
3	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5m in width as well as 10 sqm on plan including disposal of excavated earth up to 50 m and lift up to 1.5 m, disposed soil to be leveled and neatly dressed:	Sqm	300			

	All Kinds of soil					
4	Supplying, laying and jointing of the following sizes of double wall corrugated (DWC) pipes made out of HDPE conforming to IS 14930 Part II for mechanical protection to underground power cables with all required accessories in ground in the existing trench 50/38 mm or nearest size	Mtr	500			
5	Supplying and fixing 5 amps to 32 amps rating, 240/415 volts,"C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required single pole.	Each	20			
6	Supply of superior quality copper tubular cable socket and making core termination of cables of the following sizes including crimping etc. as required 10sq mm.	Each	80			
7	Supplying and laying 6 SWG GI wire at 0.50 meter below ground level for conductor earth electrode, including connection/termination with GI thimble etc. required	Mtr	100			
8	Supply and installation of 25W LED street light protection against dust and water IP65 with	Each	20			

	4Kv surge protection ,efficiency 100Lm/Watt .Aluminium diecast housing heat sink designed ,Make: Philips, Crompton or Havel's					
9	Supply and installation of weather proof outdoor box (suitable for fixing MCB) 104x104x70mm or nearest IP66.Make:Hensel KF 0404G,Sintex,Hycount	Each	20			
10	Supply and installation of fabricated 1" Dia 75cm length GI pipe suitable for fixing LED street light with clamp and accessories	Each	15			
11	Painting with synthetic enamel paint of approved brand and manufacture of required colour to an give even shade :One or more coats on old work	Sqm	80			

**Total Amount**

**( Rupees.....)**

Signature

Name & Address of the contractor

REGISTRAR