

PLD/E4/1247/Cabling & Wiring/TVKRA/2023

dated: 11.03.2024

Ref: Re-Tender Notice No. PLD/E4/1247/Cabling & Wiring/TVKRA/2023 dated 28.02.2024

Re Tender for "LT Cable laying from 62.5 KVA DG Set to admin building Server Room at Thavakkara Campus"- Last date of receiving tender- extended-reg

The last date for receiving of tender for "LT CABLE LAYING FROM 62.5 KVA DG SET TO ADMN BUILDING SERVER ROOM AT THAVAKKARA CAMPUS" is extended till 21/03/2024 at 3.00 PM.
Time of opening - 3.30 PM



Registrar



KANNUR UNIVERSITY**TENDER SCHEDULE**

NAME OF THE WORK: LT CABLE LAYING FROM 62.5 KVA DG SET TO ADMIN BUILDING SERVER ROOM AT THAVAKKARA CAMPUS

LAST DATE OF SUBMISSION: 21-03-2024 3 PM

SL NO	QUANTITY	ITEM DESCRIPTION	UNIT	RATE IN FIGURES	RATE IN WORDS	AMOUNT (Rs)
1	210	Supply and laying of one number PVC insulated and PVC sheathed armoured aluminium power cable of 1.1KV grade of the following sizes in ground including excavation of trench of size 35x75 cm,refilling the trench etc.as required but excluding sand cushioning and protective covering(in ordinary soil). 3.5Cx95 sq mm.	meter			
2	90	Supply and laying and clamping of one number PVC insulated and PVC sheathed armoured aluminium power cable of 1.1KV grade of the following sizes using clamps noted along with the cables,spacing of clamps not exceeding 60 cms,making good the damages,colour washing etc.as required 3.5Cx95 sq mm.	meter			
3	2	Supply and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed /XLPE aluminium conductor cable of 1.1KV grade as required 3.5Cx95 sq mm(45 mm).	nos			
4	3	Supply and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed /XLPE aluminium conductor cable of grade as required 3.5Cx240 sq mm(62 mm).	nos			
5	1	Supply and making straight through joint with cast resin compound including ferrules and other jointing materials for following size of PVC insulated and PVC sheathed /XLPE aluminium conductor cable of 1.1KV grade as required 3.5Cx95 sq mm.	nos			
6	3	Remove and reroute existing cable from Generator Panel to main Panel(3.5Cx240 sq mm Cable).	nos			
7	1	Preparation of drawing and documentation works including inspectorate approval.	unit			
Total Amount						
GST @ 18%						
Grand total						

(Rupees Only)

SIGNATURE:

Name & Address of the of the Contractor:

Date: