



KANNUR UNIVERSITY
(PLANNING AND DEVELOPMENT BRANCH)
NOTICE INVITING QUOTATION

PLD-D/D-2/6176/2025 (I)

14.10.2025

Sealed competitive Quotations for "**Electrical works at Dept. of Anthropology, Dr. Janaki Ammal Campus, Palayad**" are invited from registered competent Contractors/ firms. The name of work shall be superscribed on the cover.

Quotations with all details should reach the office of the Registrar, Kannur University, Kannur-02 on or before 28/10/2025 at 3 pm and the Quotations will be opened at 3:30 p.m. on the same day.

Conditions:

1. The rate quoted should be inclusive of GST and all other charges if any. The base rate, GST charges, and other charges, if any, should be furnished separately, and nothing extra shall be admissible over and above the rate quoted.
2. The Contractor shall arrange suitable materials and equipment and should be got approved by the Registrar on recommendations of the Engineer in Charge and work shall be executed as per KPWD specifications. Assistant Engineer(Electrical), Kannur University shall be the Engineer-in-charge.
3. The Contractor shall ensure that before submitting quotation for the work, the Contractor visited the site and satisfied himself about the site conditions for constructions and for logistics and smooth flow of workmen and materials as well as permission from Authorities for this purpose.
4. The Payment will be made through bank account and no advance payment will be sanctioned.
5. Work shall be completed within 30 days from the date of agreement.
6. The Defect Liability Period shall be 18 months from the date of completion of work and the contractor shall be responsible to maintain all his works till completion of the Defect Liability Period and to hand over the work to the Engineer in charge .
7. Successful Quotationer shall deposit a sum equivalent to 5 % of the value of contract as performance Guarantee within the period specified in the work order.
8. Quotation forms and details of works can be had from the www.kannuruniv.ac.in.
9. Quotation schedule is appended.

The Registrar, Kannur University reserves the right to reject any of the quotations or all the quotations without assigning any reason whatsoever.



Prof.(Dr.) Wilson V A

Development Officer (Registrar in-charge)

REGISTRAR (1/c)
KANNUR UNIVERSITY
CIVIL STATION. P. O.
KANNUR - 670 002

KANNUR UNIVERSITY						
QUOTATION SCHEDULE FOR ELECTRICAL WORK AT ANTHROPOLOGY DEPARTMENT-Dr.JANAKI AMMAL CAMPUS,PALAYAD.						
LAST DATE OF SUBMISSION:						
Sl.No	Description of work	Qty	RATE IN FIGURES	RATE IN WORDS	AMOUNT	REMARKS
1	2.3.1 Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without	1 Nos				
2	2.10.1 Supplying and fixing 5 amps to 32 amps rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.Single pole	4 Nos				
3	2.12.1 Supplying and fixing following rating, double pole, 240 volts, isolator in the existing MCB DB complete with connections, testing and commissioning etc. as required.40 amps	2 Nos				
4	90.1.1.1 Supply and laying medium gauge PVC conduit of the following sizes conforming to IS 9537/1983 Part III in roof slab, jointing the pipes with PVC solvent cement, tying & fixing the conduit firmly with the re-inforcement etc. as required.20 mm	80 mtr				
5	1.24.4 Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.3 pin 5/6 amp socket outlet	67 Nos				



6	1.22.1 Supplying and fixing metal box of following sizes (nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in front including painting etc as required.75 mm X 75 mm X 60 mm deep	1 Nos				
7	90.10.1.3 Supply & Fixing the following types/ sizes of boxes suitable for modular accessories in surface/ recess including making good the damages, colour washing etc as required (RoHS compliant)3 module moulded plastic box on surface	23 Nos				
8	90.10.1.5 Supply & Fixing the following types/ sizes of boxes suitable for modular accessories in surface/ recess including making good the damages, colour washing etc as required (RoHS compliant)6 module moulded plastic box on surface	22 Nos				
9	1.24.1 Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.5/6 amps switch	67 Nos				
10	1.28.4 Supplying and fixing following Modular base & cover plate on existing modular metal boxes etc. as required.6 Module	22 Nos				
11	1.28.2 Supplying and fixing following Modular base & cover plate on existing modular metal boxes etc. as required.3 Module	23 Nos				
12	1.17.12 Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel/ PVC conduit as required.3 x 2.5 sq. mm	150 Mtr				



13	1.17.3 Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel/ PVC conduit as required.3 X 1.5 sq.mm	150 Mtr				
	TOTAL AMOUNT					
	GST 18%					
	GRAND TOTAL					

(RupeesOnly)

SIGNATURE
Name & Address of the of the Quatationer
Date

