KANNUR UNIVERSITY
കണ്ണൂർ സർവകലാശാല

(PLANNING AND DEVELOPMENT BRANCH)

Ph: 04972-715321

General Form of File PLD/PLD-C4/18686/2026 Approved by REGISTRAR (i/c) on 05-Nov-2026 06:32 PM - Page 1

PLD/PLD-C4/18686/2026 Kannur, dated 05.11.2026

QUOTATION NOTICE

Sealed competitive quotations are invited from competent firms/contractors for undertaking the work "Electrical Wiring and Power Supply Arrangements for UPS and Air Conditioning System at the Content Creation Studio at Thavakkara Campus".

Scope of the Work:

Please see the work schedule appended.

Important Dates

Event(s)	Date & Time
Date of publishing of quotation notice	07.11.2026
Last date for submitting of quotations	13.11.2026, 03.00 PM
Opening of quotation	16.11.2026, 03.30 PM

Terms and Conditions

1. The bidder shall submit their rates in the proforma appended with this quotation notice.
2. All materials used shall be of good quality and approved by the competent authority. Inferior materials or workmanship, if noticed, shall be replaced or rectified at the contractor’s own cost.
3. The bidder shall have adequate infrastructure, manpower, and resources to execute the work efficiently within the stipulated time.
4. The contractor shall be fully responsible for the safety of workers, property, and the public during execution of the work. Adequate safety measures shall be ensured at the site.
5. Bidder should have a valid GST.
6. The University reserves the right to verify the credentials and antecedents of the bidder and to reject the quotation if any information furnished is found to be incorrect or misleading.
7. No advance payment will be sanctioned and payment will be made through the account.

The details of the work can be had from the Engineering wing of the University, Thavakkara, Kannur

on all working days up to 05.00 PM.

Sd/-
Sunil Kumar S
REGISTRAR (i/c)

To,

1. Notice Board
2. Website

General Form of File PLD/PLD-C4/18686/2026 Approved by REGISTRAR (i/c) on 05-Nov-2026 06:32 PM - Page 2

General Form of File PLD/PLD-C4/18686/2026 Approved by REGISTRAR (i/c) on 05-Nov-2026 06:32

KANNUR UNIVERSITY

SCHEDULE/SCOPE OF THE WORK

NAME OF WORK: - ELECTRICAL WIRING AND POWER SUPPLY ARRANGEMENTS FOR UPS AND AIR CONDITIONING SYSTEM AT THE CONTENT CREATION STUDIO, THAVAKKARA CAMPUS

Sl. No.	Quantity	Particulars	Unit	Rate (Excl. GST)		Amount
				Rate in figures (Rs)	Rate in words	
1. Wiring						
1.001	7.000	Supplying and fixing 5A to 32 A rating, 240/415 volts, 10 kA, ""C"" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. Single pole	Each			
1.002	1.000	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 volts, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator) 12 way, Double door	Each			
1.003	1.000	Supplying and fixing following rating, double pole, 240 volts, isolator in the existing MCB DB complete with connections, testing and commissioning etc. as required.63 amps	Each			
1.004	1.000	Supplying and fixing following rating, double pole, (single phase and neutral),240 volts, residual current circuit breaker (RCCB), having a sensitivity current 30 milli amperes in the existing MCB DB complete with connections, testing and commissioning etc. as required. 63 amps	Each			
1.005	1.000	Supplying and fixing following way, horizontal type three pole and neutral, sheet steel, MCB distribution board, 415 volts, on surface / recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator)6 Way (4+18), Double door	Each			

General Form of File PLD/PLD-C4/18686/2026 Approved by REGISTRAR (i/c) on 05-Nov-2026 06:32

1.006	1.000	Supplying and fixing following rating, double pole, 240 volts, isolator in the existing MCB DB complete with connections, testing and commissioning etc. as required. 40 amps	Each			
1.007	1.000	Supplying and fixing metal box of following sizes (nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in front including painting etc as required.75 mm X 75 mm X 60 mm deep	Each			
1.008	35.000	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc as required.Upto 35 sq. mm	Metre			
1.009	2.000	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.2 X 35 sq. mm (25mm)	Sets			
1.010	1.000	Supply and installation of 300 A Three Phase Neutral (TPN) 4 ways bus bar chamber box.	Each			
1.011	3.000	Supplying and fixing 5A to 32 A rating, 240/415 volts, 10 kA, ""C"" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. Triple pole and neutral	Each			
1.012	1.000	Supplying and fixing following rating, four pole, 415 volts, isolator in the existing MCB DB complete with connections, testing and commissioning etc. as required.100 amps	Each			
		Total				
		GST (18%)				
		Grand Total				

General Form of File PLD/PLD-C4/18686/2026 Approved by REGISTRAR (i/c) on 05-Nov-2026 06:32

Rupees …… Only		

Place & Date:

Signature, Name, Contact No, E-mail ID of the Tenderer