

KANNUR UNIVERSITY  
(Planning and Development Branch)  
NOTICE INVITING QUOTATIONS

07.05.2025

PLD/E3/4416/2020 *Part V*

Sealed competitive Quotations Superscribed as "Construction of Waste water Pit at Men's Hostel, Mangattuparamba Campus are invited from registered competent Contractors/firms. Quotations with all details should reach the office of the Registrar, Kannur University, Kannur - 02 on or before 15/05/2025 at 3 pm and the quotations will be opened at 3.30 pm on the same day.

Conditions:

1. The rate quoted should be inclusive of GST and all other charges if any. The base rate, GST charges and other charges if any should be furnished separately and nothing extra shall be admissible over and above the rate quoted
2. The contractor shall arrange all material & equipment and should be got approved by the Registrar on recommendations of the Engineer in charge and work shall be executed as per KPWD specifications.
3. The Payment will be made through bank account and no advance payment will be sanctioned.
4. Work shall be completed within one month from the date of Agreement.
5. The Engineer in Charge shall be Assistant Engineer (Civil- ,PM USHA )
6. The defect Liability period shall be 12 months from the date of completion of the work. ( as reported the Assistant Engineer (Civil- ,PM USHA ) of the University) and the contractor shall be responsible to maintain all his works till completion.
7. Successful Quotationer shall deposit a sum equivalent to 5% of value of contract as performance Guarantee within the period specified in the Work order.
8. The quotationer, before submitting the quotation for the work shall ensure that, the quotationer visited the Site and satisfied himself about the site conditions for the works (including arranging facilities of water and electricity) and for logistics and smooth flow of workmen ,and materials as well as permission from Authorities for this purpose
9. The Contractor shall make his own arrangements of Water and Electricity.
10. Quotation forms and details of works can be had from the [www.kannuruniv.ac.in](http://www.kannuruniv.ac.in).
11. Quotation Schedule is appended.

The Registrar, Kannur University reserves the right to reject any of the quotations or all the quotations without assigning any reason whatsoever.



Prof. (Dr.) Joby K Jose  
Registrar

*v*

KANNUR UNIVERSITY						
QUOTATION SCHEDULE						
Name of work: CONSTRUCTION OF WASTE WATER PIT AT MENS HOSTEL, MANGATTUPARAMBA CAMPUS						
SL. NO	QTY	PARTICULARS	UNIT	RATE		AMOUNT (RS)
				IN FIGURES (RS)	IN WORDS (RS)	
1 CIVIL WORKS						
1	6.25	2.28.1 Surface dressing of the ground including removing vegetation and inequalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to 1.5 m. All kinds of soil	Sqm			
2	7.2	2.8.1 Earth work in excavation by mechanical means (Hydraulic excavator) /manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil	Cum			
3	2.401	50.6.7.1 Laterate masonry with neatly dressed laterate stone of size 40x20x15cm or nearest size in cement mortar 1:6 for foundation and basement including all cost of materials, labour charges etc.	Cum			
4	10.801	13.1.1 12 mm cement plaster of mix: 1:4 ( 1 cement : 4 fine sand)	Sqm			
5	0.63	5.2.2 Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. up tot floor five level excluding cost of centering, shuttering, finishing and reinforcement : 1:1.5:3( 1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	Cum			

6	56.521	5.22.6 Steel reinforcement for R.C.C work including straightening, cutting, bending, placing in position and binding all complete upto plinth level Thermo - Mechanically Treated bars of grade Fe-500D or more	Kg			
7	3.762	5.9.1 Centering and shuttering including strutting, etc. and removal of form for: Foundations, footings, bases of columns, etc for mass concrete	Sqm			
8	30	50.18.9.18.1 Providing and fixing PVC pipes including fixing the pipe with clamps/clips at 1.00 m spacing. This included jointing of pipes with one step PVC solvent cement and testing of joints complete as per direction of Engineer-in-Charge 75 mm dia 6Kgf/cm2 - External work- Exposed on wall	metre			
9	10	50.18.9.8.1 Providing and fixing PVC pipes includings jointing of pipes with one step PVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. 75 mm dia 6 Kgf/ cm2	metre			
10	5	50.18.9.21.5 Providing and fixing PVC moulded fittings/ accessories for Rigid PVC pipes, including jointing with PVC solvent cement -75x75x75 mm dia Tee	nos			
11	3	50.18.9.21.4 Providing and fixing PVC moulded fittings/ accessories for Rigid PVC pipes, including jointing with PVC solvent cement - 75 mm dia Bend	nos			
TOTAL						
GST 18%						
GRAND TOTAL						
(Rupees.....Only)						

**Signature:**

**Name & Address of the Quotationer:**

**Date:**