

KANNUR UNIVERSITY
Planning & Development Branch

NOTICE INVITING RE-TENDERS

No. PLD/C1/10039/KUCL/Toilet Maintenance/2022

Dated : /09/2022

Sealed competitive Tenders are invited from registered Contractors for the Maintenance works of the Toilets at Kannur University Central Library building at Thavakkara Campus, Kannur University, Kannur-2.

Sl.No.	Name of work	EMD	Time for completing the work	Last date of submission
1	Maintenance of Toilets at Kannur University Central Library building at Thavakkara Campus, Kannur University, Kannur-2	₹ 1050/-	15 days	01-10-2022 3.00pm

Conditions

1. Tender form can be had from Kannur University website www.kannuruniversity.ac.in.
2. Cost of tender form is **Rs.300/- + (18%) GST** to be remitted separately as DD drawn in favour of The Finance Officer, Kannur University.
3. The tender, tender form and an initial agreement executed and signed in Kerala stamp Paper of value **Rs.200/-** should be sent to the University before the due date.
4. The successful tenderer should deposit a sum equivalent to **5%** of the value of the contract as Security Deposit before signing the agreement within the period specified in the letter of acceptance of the tender.
5. The rate should be inclusive of all taxes and nothing extra shall be admissible over and above the rate quoted.
6. The payment will be made through account payee cheque and no advance payment will be sanctioned.
7. Received tenders will be opened on **01/10/2022 at 3.30pm**.

The Details of work can be had from the Planning & Development Branch & Engineering wing, Thavakkara, Kannur University on all working days up to 5.00 pm.

The Registrar, Kannur University reserves the right to reject any of the tenders or all the tenders without assigning any reason whatsoever.

To

1. The Notice board
2. Website

Registrar(i/c)

QUOTATION SCHEDULE						
Name of work :- Estimate for toilet maintenance at library building at thavakkara. Date of submission :-						
SL. NO	QUANTITY	PARTICULARS	UNIT	IN FIGURES (RS)	IN WORDS (RS)	AMOUNT
1	3 nos	15.52 Dismantling of flushing cistern of all types (C.I. / PVC/ Vitrous China) including stacking of useful materials near the site and disposal of unserviceable materials within 50 metres lead	nos			
2	17.550 sqm	15.23.1 Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead.For thickness of tiles 10 mm to 25 mm	sqm			
3	6.750 sqm	11.46.1 Providing and laying Vitrified tiles indifferent sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand), including grouting the joint with white cement & matching pigments etc. complete.Size of Tile 500x500 mm	sqm			
4	10.800 sqm	8.31 Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622(thickness to be specified by the manufacturer), of approved make, in all colours,shades except burgundy, bottle green, black of any size as approved by Engineerin-Charge,in skirting, risers of steps and dados, over 12 mm thick bed of cementmortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @3.3kg per sqm,including pointing in white cement mixed with pigment of matchingshade complete.	sqm			

5	3 nos	17.18.1 Providing and fixing P.V.C. low level flushing cistern with manually controlled device (handle lever) conforming to IS: 7231, with all fittings and fixtures complete.10 litre capacity - White	nos			
6	25.000 metre	50.18.7.4.1 Providing and fixing PVC pipes, fittings including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step PVC solvent cement and testing of joints complete as per direction of Engineer-in-Charge 32 mm dia 10Kgf/cm2- Internal work - Exposed on wall	m			

TOTAL =

Rate including GST
(Rupees.....Only)

Signature:

Name & Adress of the Quotationer:

Date:

Registrar

Conditions:-

1. The quoted rate should include all taxes and nothing extra shall be admissible over and above the rate quoted.
2. The contractors shall arrange suitable materials and equipments and should be got approved by the Assistant Engineer and work shall be executed as per KPWD specifications.
3. Work shall be completed within 3 days from the date of receipt of work order.
4. The quotationer can inspect the site before submitting the quotation.