

PLANNING AND DEVELOPMENT BRANCH

NOTICE INVITING QUOTATIONS

PL D/C2/8076/Dhm_Hostel/General

10.02.2026

Sealed competitive Quotations super scribed as "**Purchase and installation of a steel wash basin (3 sink unit) at the Dharmasala Ladies Hostel Mess of Kannur University**" are invited from registered competent Contractors/firms.

Quotations with all details should reach the office of the Registrar, Kannur University, Kannur-2 on or before 26/02/2026 at 3.00 pm and the Quotations will be opened at 3.30 pm on the same day.

Conditions:

1. The rate quoted should be **inclusive of GST and all other charges if any**. The base rate, GST charges and other charges if any should be furnished separately and nothing extra shall be admissible over and above the rate quoted.
2. The Contractor shall arrange suitable materials and equipment and should be got approved by the Assistant Executive Engineer and work shall be executed as per KPWD specifications.
3. The Payment will be made through bank account and no advance payment will be sanctioned.
4. The successful bidder will be required to deposit Performance Guarantee/Security Deposit as per rules.
5. Work shall be completed within **3 months** from the date of agreement.
6. A defect liability period is **1 year** from the date of completion of work .
7. Quotation forms and details of works can be had from the **www.kannuruniv.ac.in**.
8. The Registrar, Kannur University reserves the right to reject any of the quotations or all the quotations without assigning any reason whatsoever.
9. Quotation schedule is appended herewith.


Sunil Kumar S
Registrar

To

1. Notice Board
2. Website



KANNUR UNIVERSITY						
<u>QUATATION SCHEDULE</u>						
Name of work: KANNUR UNIVERSITY-WASH BASIN FOR DHARMASHALA LADIES HOSTEL						
SL. NO	PARTICULARS	QTY	UNIT	RATE		AMOUNT (RS)
				IN FIGURES (RS)	IN WORDS (RS)	
1 CIVIL WORKS						
1	OD229913/2025-2026. SS Hand wash unit with bottom front side half portion overing. Legs using 1 1/2 " square tubes with adjustable nylon boots leg using size:180X55X85+15cms (SS 304).	1.000	each			
2	18.50.1. Providing and fixing C.P brass long nose bib cock of approved quality conforming to IS standards and weighing not less than 810 gms.15 mm nominal bore	3.000	each			
3	50.18.9.12.2. Providing and fixing PVC pipes, fittings including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step PVC solvent cement and testing of joints complete as per direction of Engineer-in-Charge 20 mm dia 10Kgf/cm2 External work- Exposed on wall	6.000	metre			
4	50.18.9.13.2. Providing and fixing PVC pipes, fittings including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step PVC solvent cement and testing of joints complete as per direction of Engineer-in-Charge 25 mm dia 10 Kgf/cm2- External work - Exposed on wall	6.000	metre			
5	50.18.9.14.2. Providing and fixing PVC pipes, fittings including fixing the pipe with clamps at 1.00 m spacing. this includes jointing of pipes & fittings with one step PVC solvent cement and testing of joints complete as per direction of Engineer-in-Charge 32 mm dia 6 Kgf/cm2 - External work - Exposed on wall	6.000	metre			

6	50.18.9.17.1. Providing and fixing PVC pipes including fixing the pipe with clamps/ clip at 1.00 m spacing . This includes jointing of pipes with one step PVC solvent cement and testing of joints complete as per direction of Engineer-in-Charge 63 mm dia 6 Kgf/cm2 - External work - Exposed on wall	6.000	metre			
7	2.8.1. Earth work in excavation by mechanical means (Hydraulic excavator) /manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.All kinds of soil	1.440	cum			
8	13.1.1. 12 mm cement plaster of mix:1:4 (1 cement : 4 fine sand)	0.400	sqm			
9	13.43.1. Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface:Water thinnable cement primer	0.400	sqm			
10	13.60.1. Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade:Two or more coats on new work	0.400	sqm			
TOTAL						
GST 18%						
GRAND TOTAL						
(Rupees						Only)

Signature:

REGISTRAR

Name & Address of the Quotationer: Date: