

KANNUR UNIVERSITY  
(Planning and Development Branch)  
NOTICE INVITING QUOTATIONS

PLD/E3/4416/2020 *Part VI*

06.09.2024

Sealed competitive Quotations Superscribed as "Maintenance Works at Ladies Hostel In Mangattuparamba Campus" are invited from registered competent Contractors/firms.

Quotations with all details should reach the office of the Registrar, Kannur University, Kannur -02 on or before 19.09.2024 at 3pm and the quotations will be opened at 3.30pm on the same day.

Conditions:

1. The rate quoted should be inclusive of GST and all other charges if any. The base rate, GST charges and other charges if any should be furnished separately and nothing extra shall be admissible over and above the rate quoted
2. The contractor shall arrange all material & equipment and should be got approved by the Registrar on recommendations of the Engineer in charge and work shall be executed as per KPWD specifications.
3. The Payment will be made the through bank account and no advance payment will be sanctioned.
4. Work shall be completed within 6 months from the date of Agreement.
5. The defect Liability period shall be 18 months from the date of completion of the work. ( as reported the Executive Engineer of the University) and the contractor shall be responsible to maintain all his works till completion.
6. Successful Quotationer shall deposit a sum equivalent to 5% of value of contract as performance Guarantee within the period specified in the Work order.
7. The quotationer, before submitting the quotation for the work shall ensure that, the quotationer visited the Site and satisfied himself about the site conditions for the works (including arranging facilities of water and electricity) and for logistics and smooth flow of workmen ,and materials as well as permission from Authorities for this purpose
8. The Contractor shall make his own arrangements of Water and Electricity.
9. Quotation forms and details of works can be had from the [www.kannuruniv.ac.in](http://www.kannuruniv.ac.in).
10. Quotation Schedule is appended.

The Registrar, Kannur University reserves the right to reject any of the quotations or all the quotations without assigning any reason whatsoever.



Prof. (Dr.) Joby K Jose  
Registrar



**KANNUR UNIVERSITY**

QUOTATION SCHEDULE

**NAME OF THE WORK: MAINTENANCE WORKS AT LADIES HOSTEL IN MANGATTUPARAMBA CAMPUS.**

		LAST DATE OF SUBMISSION:				
SL NO	QUANTITY	ITEM DESCRIPTION	UNIT	RATE IN FIGURES (WITHOUT GST)	RATE IN WORDS	AMOUNT (WITHOUT GST)
<b>1. GATE REPAIR WORKS</b>						
1	0.900	15.10.2 Dismantling dressed stone work ashlar face stone work, marble work or precast concrete work manually / by mechanical means including stacking of serviceable and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-Charge: In cement mortar	cum			
2	3.744	2.9.2 Excavation work by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m. Hard rock (requiring blasting)	cum			

3	0.243	5.1.3 Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level:1:2:4 ( 1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	cum			
4	1.686	5.1.2 Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level:1:1:5:3 (1 cement 1.5 coarse sand :3 graded stone aggregate 20 mm nominal size)	cum			
5	5.217	5.9.1 Centering and shuttering including strutting, etc. and removal of form for:Foundations, footings, bases of columns, etc for mass concrete	sqm			
6	170.00	5.22.6 Steel reinforcement for R.C.C work including straightening, cutting, bending, placing in position and binding all complete upto plinth levelThermo - Mechanically Treated bars of grade Fe-500D or more	kg			
7	0.901	50.6.7.1 Laterate masonry with neatly dressed laterate stone of size 40x20x15cm or nearest size in cement mortar 1:6 for foundation and basement including all cost of materials, labour charges etc.	cum			
8	0.601	od370812/2023_2024 Laterate masonry with available reusable laterate stone of size 35x20x15 cm or nearest size in cement mortar 1:6 for superstructure above floor two level upto floor five level including labour charges etc.	cum			

9	23.800	13.1.1 12 mm cement plaster of mix:1:4 ( 1 cement : 4 fine sand)	sqm			
10	25.00	10.25.2 Item Shifted to head 14 as item 14.74 Steel work welded in built up sections/framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	kg			
11	10.50	13.62.1 Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture .	sqm			
12	23.80	13.60.1 Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade: Two or more coats on new work	sqm			

2.SHEET WORK

1	64	50.10.1 Steel work in built up G I tubular ( round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete	kg	
2	8	12.50 Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+0.05%), total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling/self tapping screws of size (5.5x55mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	sqm	
<b>TOTAL AMOUNT (WITHOUT GST)</b>				
<b>ADD GST 18%</b>				
<b>TOTAL AMOUNT (Including GST)</b>				
Rupees.....				

SIGNATURE

NAME & ADDRESS OF THE CONTRACTOR