



KANNUR UNIVERSITY

(PLANNING AND DEVELOPMENT BRANCH)

NOTICE INVITING QUOTATION

PLD/E5/16402/2025

20.01.2026

Sealed competitive Quotations for "Dismantling partition wall in between classrooms 104 &105 at main block, Dr. Janaki Ammal Campus, Palayad" are invited from registered competent Contractors/ firms. The name of work shall be superscribed on the cover.

Quotations with all details should reach the office of the Registrar, Kannur University, Kannur-02 on or before 03/02/2026 at 3 pm and the Quotations will be opened at 3.30p.m on the same day.

Conditions:

1. The rate quoted should be inclusive of GST and all other charges if any. The base rate, GST charges and other charges if any should be furnished separately and nothing extra shall be admissible over and above the rate quoted.
2. The Contractor shall arrange suitable materials and equipment and should be got approved by the Registrar on recommendations of the Engineer in Charge and work shall be executed as per KPWD specifications. Asst. Executive Engineer(Civil), Kannur University shall be the Engineer-in-charge.
3. The Contractor shall ensure that before submitting quotation for the work, the Contractor visited the site and satisfied himself about the site conditions for constructions and for logistics and smooth flow of workmen and materials as well as permission from Authorities for this purpose.
4. The Payment will be made through bank account and no advance payment will be sanctioned.
5. Work shall be completed within 1 month from the date of agreement.
6. The Defect Liability Period shall be 1 year from the date of completion of work and the contractor shall be responsible to maintain all his works till completion of the Defect Liability Period and to hand over the work to the Engineer in charge .
7. Successful Quotationaler shall deposit a sum equivalent to 5 % of the value of contract as security deposit within the period specified in the work order.
8. Quotation forms and details of works can be had from the [www.kannuruniv.ac.in](http://www.kannuruniv.ac.in).
9. Quotation schedule is appended.

The Registrar, Kannur University reserves the right to reject any of the quotations or all the quotations without assigning any reason whatsoever.

Sd/-

Prof. (Dr.) Joby K Jose  
Registrar



KANNUR UNIVERSITY						
<u>QUOTATION SCHEDULE</u>						
Name of work: DISMANTLING PARTITION WALL BETWEEN CLASS ROOMS 104&105 AT MAIN BLOCK Dr. JANAKI AMMAL CAMPUS, PALAYAD						
SL. NO	QTY	PARTICULARS	UNIT	RATE		AMOUNT (RS)
1 CIVIL WORKS						
1	5.508	15.7.4 Demolishing brick work manually / by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-Charge.In cement mortar	Cum			
2	2.43	11.37 Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), Jointing with grey cement slurry @ 3.3 kg/sqm including pointing the joints with white cement and matching pigment etc.,complete	Sqm			
3	1.36	13.1.2 12 mm cement plaster of mix:1:6 (1 cement : 6 fine sand). Plastering	Sqm			
4	1.36	13.43.1 Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface:Water thinnable cement primer	Sqm			
5	1.36	13.60.1 Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade:Two or more coats on new work	Sqm			



6	1	OD187015/2025-2026 engaging labour for clearing the site	day			
		<b>TOTAL</b>				
		<b>GST 18%</b>				
		<b>GRAND TOTAL</b>				
<b>(Rupees.....Only)</b>						

**Signature:**

**Name & Address of the Quotationer:**

**Date:**

