

PLANNING AND DEVELOPMENT BRANCH

NOTICE INVITING QUOTATIONS

PLD-E/E1/1839/2025

08.06.2026

Sealed competitive Quotations super scribed as "Drainage work at School of Pedagogical Sciences, Dharmashala campus of Kannur University" are invited from registered competent Contractors/firms.

Quotations with all details should reach the office of the Registrar, Kannur University, Kannur-2 on or before 23/06/2026 at 3.00 pm and the Quotations will be opened at 3.30 pm on the same day.

Conditions:

1. The rate quoted should be **inclusive of GST and all other charges if any**. The base rate, GST charges and other charges if any should be furnished separately and nothing extra shall be admissible over and above the rate quoted.
2. The Contractor shall arrange suitable materials and equipment and should be got approved by the Assistant Executive Engineer and work shall be executed as per KPWD specifications.
3. The Payment will be made through bank account and no advance payment will be sanctioned.
4. The successful bidder will be required to deposit Performance Guarantee/Security Deposit as per rules.
5. Work shall be completed within **3 Months** from the date of agreement.
6. A Defect liability period of 6 months will be applicable for this work, after completion.
7. Quotation forms and details of works can be had from the www.kannuruniv.ac.in.
8. The Registrar, Kannur University reserves the right to reject any of the quotations or all the quotations without assigning any reason whatsoever.
9. Quotation schedule is appended herewith.

sd/-

Registrar

To

1. Notice Board
2. Website



QUOTATION SCHEDULE						
DRAINAGE WORK AT SCHOOL OF PEDAGOGICAL SCIENCES, DHARMASHALA CAMPUS						
SL. NO	QTY	PARTICULARS	UNIT	RATE INCLUDING ALL TAXES		AMOUNT
				IN FIGURES	IN WORDS	
1	6.039	2.8.1 Earth work in excavation by mechanical means (Hydraulic excavator) /manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.All kinds of soil	Cum			
2	1.17	4.1.8 Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources)	Cum			
3	2.85	50.6.1.7 Solid block masonry using pre cast solid blocks (Factory made) of size 40x20x15cm or nearest available size confirming to IS 2185 part I of 1979 for foundation and plinth with thickness 15 cm in : CM 1:6 (1 cement : 6 coarse sand) etc complete	Cum			
4	1.92	5.9.3 Centering and shuttering including strutting, etc. and removal of form for:Suspended floors, roofs, landings, balconies and access platform	Sqm			
5	0.144	5.1.3 Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level:1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	Cum			
6	10.8	5.22.6 Steel reinforcement for R.C.C work including straightening, cutting, bending, placing in position and binding all complete upto plinth levelThermo - Mechanically Treated bars of grade Fe-500D or more	kg			
7	20	13.1.2 12mm cement plaster of mix:1:6 (1 cement : 6 fine sand).	Sqm			
TOTAL						

(Rupees.....Only)

Signature:

Name & Adress of the Quotationer:

REGISTRAR