

PLD/E3/5465/FP/CLC/14

dated : 30.09.2024

Ref: Tender Notice No. PLD/E3/5465/FP/CLC/14 dated 09 .09.2024

Tender for "Rectification Work of Fire Protection including Commissioning at Academic Staff College Building (MMTTC/ HRDC) at Thavakkara Campus, Kannur University "- Last date of receiving tenders- extended-reg

The last date for receiving of tender for "Rectification Work of Fire Protection including Commissioning at Academic Staff College Building (MMTTC/ HRDC) at Thavakkara Campus, Kannur University " is extended till 14/10/2024 at 3.00 PM. Time of opening - 3.30 PM

Sd/-
Registrar



KANNUR UNIVERSITY
(PLANNING AND DEVELOPMENT BRANCH)
NOTICE INVITING TENDERS

PLD/E3/5465/FP/CLC/14

09.09.2024

Sealed competitive tenders superscribed as "Rectification Work of Fire Protection including Commissioning at Academic Staff College Building (MMTTC/HRDC) at Thavakkara Campus, Kannur University" are invited from registered competent Contractors/firms.

Sl.No	Name of Work	EMD	Tender Fee	Time for the completion of work	Last date of submission
1	2	3	4	5	6
1	Rectification Work of Fire Protection including Commissioning at Academic Staff College Building (MMTTC/HRDC) at Thavakkara Campus, Kannur University	Rs.12,340/-	Rs.990/- Plus GST @ 18%	six months from the date of Agreement	30.09.2024 3.00 PM

1. Tender Form can be had from Kannur University Website www.kannuruniversity.ac.in.
2. A sum of Rs.990/-plus GST @18%) towards the cost of Tender form and an amount of Rs.12,340/- as EMD should be remitted **separately** by way of Demand Draft drawn in favour of Finance Officer, Kannur University, payable at SBI South Bazar Branch, Kannur or Kannur Branch of any other Nationalized or scheduled Bank.
3. The Tenderer should send along with the tender an initial agreement executed and signed in Kerala Stamp Paper of value ₹.200/-
4. The Tenderer shall have valid GST registration and shall furnish a copy of registration certificate along with the tender documents.
5. The successful Tenderer before signing the Agreement and within the period specified in the work order, shall deposit a sum equivalent to 5% of the value of the contract as Security Deposit.
6. The rate quoted should be inclusive of GST and all other charges if any. The base rate, GST charges and other charges if any should be furnished separately and nothing extra shall be admissible over and above the rate quoted.
7. The Contractor before submitting Tender for the work shall ensure that, they have visited the Site and satisfied himself about the site conditions for the work

(including arranging facilities of water and electricity) and for logistics and smooth flow of workmen ,and materials as well as permission from Authorities for this purpose

8. Payment will be made through account and no advance payment will be sanctioned
9. The Validity period of Tendered amount shall be 2 months.
10. Defect Liability for the work shall be 3 years from the date of satisfactory completion of the work.
11. Received tenders will be opened on 30.09.2024 at 3.30 PM .
12. Details of work can be had from the Planning and Development Branch on all working days up to 5 pm.

The Registrar, Kannur University, reserves the right to reject any of the tenders or all the tenders without assigning any reason whatsoever.



Prof. (Dr.) Joby K Jose
Registrar



To

1. Notice Board
2. Website

KANNUR UNIVERSITY

TENDER SCHEDULE

NAME OF THE WORK: Rectification work of Fire Protection including commissioning at Academic staff college building (MMTTC/HRDC) at Thavakkara Campus, Kannur University

LAST DATE OF SUBMISSION: 30.09.2024

SL NO	QUANTITY	ITEM DESCRIPTION	UNIT	RATE IN FIGURES (WITHOUT GST)	RATE IN WORDS	AMOUNT (WITHOUT GST)
Rectification work of Fire Protection including commissioning						
1		Supplying and installing in position of self glowing sign boards of size 100mm X 300mm made of luminescent safely, rigid sheet in green colour, photo luminescent with two each hanging chains & necessary supports to hang it on ceiling, as per standard.				
	14	" EXIT " sign boards	Nos			
	7	" FIRE EXIT " sign boards	Nos			
	7	"FIRE LIFT" sign boards.	Nos			
	1	"FIRE CONTROL ROOM" sign board.	Nos			
	7	"FLOOR IDENTIFICATION " sign boards.	Nos			
	2	"ASSEMBLY AREA " sign board.	Nos			
2	7	Supplying and installing in position suitable size of LED "FIRE DUCT" sign boards with battery back up.	Nos			
3	7	Supplying and installing in position suitable size of LED "FIRE EXIT" sign boards with battery back up.	Nos			
4	1	FIRE ALARM CONTROL PANEL :- Supply, Installation, Testing and Commissioning of 8 Zone Fire Alarm Control Panel conventional type, micro processor based control panel, made of MS powder coated CRCA sheet with audio and visual display & supplied with all standard mounting accessories.	Nos			
5	1	Supply, installation, testing and commissioning of 8 Zone public address and talk back system consisting of multiple zone public address cum talkback console with mike and selector. multiple channel talk back master control panel with 2x16 character LCD display, power supply, battery charger, battery housing, 80 W PA mic, multiple channel selector with all call and mic on. The console shall be provided with suitable capacity amplifier (min 80W) and suitable capacity battery (min 12V) all assembled in a cabinet.	Nos			
6	7	Supply, installation, testing and commissioning of Two Way Talk Back Speaker with Call switch 6 watts wall mounted PA Speaker in CRCA sheet fabricated with LMT for talk back facility with call switch.	Nos			
7	6	Supply, laying, testing commissioning of C class heavy duty MS pipe conforming to IS 1239 including fittings like elbows, tees flanges, tapers, nuts bolts, gaskets etc., fixing the pipe on the wall/ceiling with suitable clamps and painting with one coat of primer and two coats of synthetic enamel (Signal red) paint of required shade 100 mm dia	Nos			

SL NO	QUANTITY	ITEM DESCRIPTION	UNIT	RATE IN FIGURES (WITHOUT GST)	RATE IN WORDS	AMOUNT (WITHOUT GST)
8	3000	Supplying, laying, testing and commissioning of 2 runs of 1 sq.mm cross section PVC insulated FIRE RATED COPPER WIRES in the PVC conduits. (Extension of Fire Alarm Panel and PA/Talkback system cabling)	Mtr			
9	1000	Supplying, installing, testing and commissioning approved make PVC 20mm dia CONDUITS on ceiling / wall / floor etc. complete with accessories like, Junction boxes, saddle clip,Bends etc. Make:- ISI Branded	Mtr			
10	1	Supplying, installing, testing and commissioning of Pressure Gauge	Nos			
11	1	Supplying, installing, testing and commissioning of Pressure Switch	Nos			
12	1	Supplying and Installing of Emergency and Escape lighting, with alternate power supply for Main and Fire stair with 1KVA UPS System with battery &Wiring used with fire rated 1.5Sqmm cable through 25mm conduit with necessary protection and Power supply socket for each signage LED and UPS	Set			
13	75	Removing colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete and painting with one coat of primer and two coats of synthetic enamel (Signal red) paint	Sqm			
14	1	Preparation and submission of fire drawings and obtaining final NOC from Kerala Fire Rescue Service department. (Include Laminated escape route plan and other required drawings)	Job			
Total amount (Without GST)						
ADD GST 18%						
Grand total amount (Including GST)						

*Rate including GST

(RupeesOnly)

SIGNATURE

Name & Address of the of the tenderer

Date