

**KANNUR UNIVERSITY**  
**Planning & Development Branch**

**NOTICE INVITING TENDERS**

No.PLD/C1/2752/Shifting Battery Room/TVKRA/2022

Dated: 04/08/2022

Sealed competitive Tenders are invited from the registered Contractors for the UPS room A/C installation, Wiring works, Construction of Partition wall between the UPS room and Server room at the Administrative Block at the Thavakkara campus of the University.

The details are furnished below.

Sl.No.	Name of work	EMD	Time for completing the work	Last date of submission
1	Construction of Partition wall between UPS room and Server room, A C installation and Wiring works in the UPS Room, at the Administrative Block at Thavakkara Campus, Kannur University	₹ 3400	30 days	31-08-2022 3 P.M.

**Conditions**

1. Tender form can be had from Kannur University website [www.kannuruniversity.ac.in](http://www.kannuruniversity.ac.in).
2. Cost of Tender form is Rs.500/ + 18% GST to be remitted separately as DD drawn in favour of The Finance Officer, Kannur University.
3. The Tender, tender form and an initial agreement executed and signed in Kerala stamp Paper of value Rs.200/- should be sent to the University before the due date.
4. The successful tenderer should deposit a sum equivalent to 5% of the value of the contract as Security Deposit before signing the agreement within the period specified in the letter of acceptance of the tender.
5. The rate should be inclusive of all taxes and nothing extra shall be admissible over and above the rate quoted.
6. The payment will be made through account payee cheque and no advance payment will be sanctioned.
7. Received tenders will be opened on **31-08-2022** at 3.30 pm.

The Details of work can be had from the Planning & Development Branch, Thavakkara, Kannur University on all working days up to 5.00 pm. The Registrar, Kannur University reserves the right to reject any of the Tenders or all the Tenders without assigning any reason whatsoever.

sd/-  
**REGISTRAR(i/c)**

To

1. Notice board
2. Website

QUOTATION SCHEDULE						
Name of work :- UPS room A/C installation , wiring works ,Partition wall between UPS room and server room in AD building at Thavakkara campus						
						Date of submission :-
SL. NO	QUANTITY	PARTICULARS	UNIT	IN FIGURES (RS)	IN WORDS (RS)	AMOUNT
<b>(A) Electrical works</b>						
<b>1. A/C Wiring works</b>						
1	20 mtr	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel/ PVC conduit as required.3 x 4 sq. mm	mtr			
2	15 mtr	Supplying and fixing of following sizes of medium class PVC conduit along with accessories in surface/ recess including cutting the wall and making good the same in case of recessed conduit as required.20 mm	mtr			
3	1 no	Supply and Fixing the following modular switches & accessories in the existing front plates and giving necessary connections as required (RoHS compliant )32A DP switch with indicator	no			
4	1 no	Supplying and fixing 5 amps to 32 amps rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.Single pole	no			
5	1 no	Supplying and fixing following size/ modules, GI box alongwith modular base & cover plate for modular switches in recess etc as required.1 or 2 Module (75mmX75mm)	no			
6	15 mtr	A/C drain piping	mtr			
<b>2. A/C Installation works</b>						
1	1 no	Supply ,installation,testing and commissioning of 1.5 ton inverter type A/C including copper piping (8mtr) including cost and conveyence of materials etc. as per standard specification	item			

<b>( B ) Civil works    Partition wall between UPS room and server room in AD building</b>						
1	1.16 sqm	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles above 25 mm and up to 40 mm	sqm			
2	20.88 sqm	Dismantling cement asbestos or other hard board ceiling or partition walls including stacking of serviceable materials and disposal of unserviceable materials within 50 metres lead.	sqm			
3	4.176 cum	Providing and laying autoclaved aerated cement blocks masonry with 100 mm thick AAC blocks in superstructure above floor 2 level up to floor V level in cement mortar 1:4 (1 cement :4 coarse sand). The rate includes providing and placing in position 2 Nos 6 mm dia M.S. bars at every third course of masonry work.	cum			
4	41.76 sqm	12 mm cement plaster of mix:1:4 ( 1 cement : 4 fine sand)	sqm			
5	41.76 sqm	Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade:Two or more coats on new work	sqm			
6	0.5 cum	Dismantling existing partition	cum			

**TOTAL =**

**Rate including GST  
(Rupees.....Only)**

**Signature:**

**Name & Adress of the Quotationer:**

**Date:**

**Registrar**

Conditions:-

1. The quoted rate should include all taxes and nothing extra shall be admissible over and above the rate quoted.
2. The contractors shall arrange suitable materials and equipments and should be got approved by the Assistant Engineer and work shall be executed as per KPWD specifications.
3. Work shall be completed within 3 days from the date of receipt of work order.
4. The quotationer can inspect the site before submitting the quotation.