



KANNUR UNIVERSITY
(PLANNING AND DEVELOPMENT BRANCH)
NOTICE INVITING QUOTATIONS

No.PID/E1/9465/NAAC/2021

Dated 30.09.2021

Sealed competitive Quotations super scribed as 'Construction of Ramp for computer Lab at Payyannur campus" are invited from registered firms/contractors for the Payyannur Campus of Kannur University.

Quotations with all details should reach the office of the Registrar ,Kannur University,Kannur-02 on or before 11.10.2021 at 3pm and the quotations will be opened at 3.30pm on the same day.

Conditions:

1. The rate should be inclusive of all taxes and nothing extra shall be admissible over and above the rate quoted.
2. Material should be got approved by the Executive Engineer/Assistant Engineer and work shall be executed as per KPWD specifications .
3. Payment will be made through account and no advance payment will be sanctioned.
4. Work shall be completed within 20days from the date of receipt of work order.
5. Quotation schedule can be had from Kannur University Website www.kannuruniversity.ac.in
6. Details of work can be had from the Engineering wing of the Kannur University on all working days up to 5 pm.

The Registrar, Kannur University reserves all the right to reject any of the quotations or all the quotations without assigning any reason whatsoever.


REGISTRAR(i/c)

To,

1. Notice Board.
2. Website
3. Notice Board , Payyannur Campus.

Copy to : EE/ AE-civil / PA to R

KANNUR UNIVERSITY
QUOTATION SCHEDULE

NAME OF THE WORK: CONSTRUCTION OF RAMP FOR COMPUTER LAB AT PAYYANUR CAMPUS

SL. NO	QTY	PARTICULARS	UNIT	RATE IN FIGURES	AMOUNT IN FIGURES	REMARKS
1	3.80	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles 10 mm to 25 mm	sqm			
2	90.8	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	kg			
3	29.2	Steel work in built up G I tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete	kg			
4	420	supplying and fixing 8mm thick approved quality iron Chequered plate	kg			
5	16.9	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade: Two or more coats on new work	sqm			
		TOTAL				

Signature:

Name & Address of the Quotationer:

Date: