

Prof.N. K Deepak,
Campus Director.

KU-SAT-CD/General /2015

Date: 09.07.2026

QUOTATION RE-NOTICE

Sealed competitive Quotations superscribed as "Installation of Pipeline for rainwater tank in the SAT Campus " are invited from competent Contractors/firms.

Completed Quotations should on the address **Campus Director, Swami Ananda Theertha Campus, Kannur University, Payyannur, Edat P.O, Pin 670327 on or 16 .07.2026 at 3.P.M** and will be opened at 4.00 PM, the same day.

Conditions:


1. The rate quoted should be inclusive of GST and all other charges if any. The base rate, GST charges and other charges if any should be furnished separately and nothing extra shall be admissible over and above the rate quoted (estimate amount is Rs. 60000/-).
2. The Contractor shall arrange all material & equipment and should be got approved by the Engineer in Charge and work shall be executed as per KPWD specifications.
3. Payment will be made through bank account and no advance payment will be sanctioned.
4. The Quotationer, before submitting Quotation for the work shall ensure that, the Quotationer visited the Site and satisfied himself about the site conditions (including arranging facilities of water and electricity) and for logistics and smooth flow of workmen, and materials as well as permission from Authorities for this purpose.
5. Work shall be completed within 10 days from the date of work is granted
6. The Engineer in Charge shall be Assistant executive engineer.

Details of the Work

The work includes excavation of a trench along the revised alignment, laying of the underground (UG) pipe with proper positioning and necessary safety measures, construction of a manhole, and refilling the trench with the excavated soil including proper compaction. The

proposed work aims to ensure uninterrupted flow of rainwater from the building in the campus to the existing Rain water pit.

The Campus Director, Swami Aanandha theertha Campus, Kannur University reserves the right to reject any of the quotations or all the quotations without assigning any reason whatsoever.


Campus Director



PROF. N. K. DEEPAK
CAMPUS DIRECTOR
KANNUR UNIVERSITY
SWAMI ANANDATHEERTHA CAMPUS
EDAT P.O., PAYYANUR-670 327

Swami Anandhateertha Campus, Kannur University
Quotation Schedule

Name of Work	Particulars	Qty	Unit	Rate		Amount
1.001	2.10.1.2 Excavating trenches of required width for pipes, cables, etc including excavation for sockets, and dressing of sides, ramming of bottoms, depth up to 1.5 m, including getting out the excavated soil. And then returning the soil as required, in layers not exceeding 20 cm in depth, including consolidating each deposited layer by ramming, watering, etc. and disposing of surplus excavated soil as directed, within a lead of 50m.	10.824	m			
1.002	50.6.2.1 Solid block masonry using pre cast solid blocks (Factory made) of size 30x20x15 cm or nearest available size confirming to IS 2185 part I of 1979 for foundation and plinth with thickness 15cm in: CM 1:6 (1 cement :6 coarse sand) etc complete	0.180	cum			
1.003	4. 1.5 Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1 :3:6 (1 Cement : 3 coarse sand (zone-II) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources	0.049	cum			
1.004	5. 1.3 Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level: 1 :2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	0.074	cum			

1.005	5.22.6 Steel reinforcement for R.C.C work including straightening, cutting, bending, placing in position and binding all complete up to plinth level thermo - Mechanically Treated bars of grade Fe-500D or more (manhole cover slab)	2.765	kg			
1.006	19.3.5 Providing and laying cement concrete 1:5:10 (1 cement:5 coarse sand : 10 graded stone aggregate 40 mm nominal size) up to haunches of S.W. pipes including bed concrete as per standard design:300 mm diameter S.W. pipe	30	m			
	Total					
	Tax					
	Grand Total					
	Amount in words					)



Name of the quotationer

Sign