



KANNUR UNIVERSITY
(PLANNING AND DEVELOPMENT BRANCH)
NOTICE INVITING TENDERS

PLD/E3/8120/2022

07.02.2026

Sealed competitive tenders superscribed as" REPAIR WORK OF DAMAGED COMPOUND WALL AT MANGATTUPARAMBA CAMPUS, Kannur University" are invited from registered competent Contractors/firms.

Sl.No	Name of Work	EMD	Tender Fee	Time for the completion of work	Last date of submission
1	2	3	4	5	6
1	REPAIR WORK OF DAMAGED COMPOUND WALL AT MANGATTUPARAMBA CAMPUS, Kannur University.	Rs.6,725/-	Rs.635/- including GST @ 18%	.6 months	20/02/2026 at 3.00pm

1. Tender Form can be had from Kannur University Website www.kannuruniversity.ac.in.
2. A sum of Rs.635 (including GST @18%) towards the cost of Tender form and an amount of Rs.6,725/- as EMD should be remitted **separately** by way of Demand Draft drawn in favour of Finance Officer, Kannur University, payable at SBI South Bazar Branch, Kannur or Kannur Branch of any other Nationalized or scheduled Bank.
3. The Tenderer shall have valid GST registration and shall furnish a copy of registration certificate along with the tender documents.
4. The successful Tenderer before signing the Agreement and within the period specified in the work order, shall deposit a sum equivalent to 5% of the value of the contract as Security Deposit.
5. The rate quoted should be inclusive of GST and all other charges if any. The base rate, GST charges and other charges if any should be furnished separately and nothing extra shall be admissible over and above the rate quoted.
6. The Contractor before submitting Tender for the work shall ensure that, they have visited the Site and satisfied himself about the site conditions for the work (including arranging facilities of water and electricity) and for logistics and smooth flow of workmen ,and materials as well as permission from Authorities for this purpose
7. Payment will be made through account and no advance payment will be sanctioned



8. Defect Liability for the work shall be **3 years** from the date of satisfactory completion of the work.
9. Received tenders will be opened on 29/02/2026 at 2:30 pm
10. Details of work can be had from the Planning and Development Branch on all working days up to 5 pm.

The Registrar, Kannur University, reserves the right to reject any of the tenders or all the tenders without assigning any reason whatsoever.

sd/-

Prof. (Dr.) Joby K Jose
Registrar

To

1. Notice Board
2. Website



KANNUR UNIVERSITY

TENDER SCHEDULE

REPAIR WORK OF DAMAGED COMPOUND WALL AT MANGATTUPARAMBA CAMPUS

SL. NO	QTY	PARTICULARS	UNIT	RATE	AMOUNT (RS)
		REPAIR WORK OF DAMAGED COMPOUND WALL			
1	255.000	2.28.1 Surface dressing of the ground including removing vegetation and in-equalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to 1.5 m. All kinds of soil	sqm		
2	255.000	2.31 Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth up to 30 cm measured at a height of 1 m above ground level and removal of rubbish up to a distance of 50 m outside the periphery of the area cleared	sqm		
3	7.073	15.7.4 Demolishing brick work manually / by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-Charge. In cement mortar	cum		
4	1.683	5.1.2 Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level: 1:1.5:3 (1 cement 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	cum		
5	10.200	5.9.1 Centering and shuttering including strutting, etc. and removal of form for: Foundations, footings, bases of columns, etc for mass concrete	sqm		



6	134.640	5.22.6 Steel reinforcement for R.C.C work including straightening, cutting, bending, placing in position and binding all complete upto plinth level Thermo - Mechanically Treated bars of grade Fe-500D or more	kg		
7	14.280	50.6.7.2 Laterate masonry with neatly dressed laterate stone of size 40x20x15cm or nearest size in cement mortar 1:6 for super structure above plinth level up to floor two level including all cost of materials, labour charges etc.	cum		
8	1.767	4.1.3 Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:2:4 (cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	cum		
9	44.200	5.9.5 Centering and shuttering including strutting, etc. and removal of form for: Lintels, beams, plinth beams, girders bressumers and cantilevers	sqm		
		TOTAL			
		GST 18%			
		GRAND TOTAL			

(Rupees.....Only)

Signature:

Name & Address of the Quotationer:

Date:

