



KANNUR UNIVERSITY
(PLANNING AND DEVELOPMENT BRANCH)
NOTICE INVITING RE QUOTATIONS

No.PID/E1/Rain Water harvesting/NAAC/2021

Dated:07.09.2021

Sealed competitive Quotations **superscribed as "Rain water harvesting work at Mangattuparamba Campus of Kannur University"** are invited from registered firms/contractors .

Quotations with all details should reach the office of the Registrar, Kannur University, Kannur-02 on or before 16.09.2021 at 3pm and the quotations will be opened at 3.30pm on the same day.

Conditions:

1. The rate should be inclusive of all taxes and nothing extra shall be admissible over and above the rate quoted.
2. Material should be got approved by the Executive Engineer/Assistant Engineer and work shall be executed as per KPWD specifications .
3. Payment will be made through account and no advance payment will be sanctioned.
4. Work shall be completed within one month from the date of receipt of work order.
5. Quotation schedule can be had from Kannur University Website www.kannuruniversity.ac.in
- 6.Details of work can be had from the Engineering wing of the Kannur University on all working days up to 5 pm.

The Registrar, Kannur University reserves all the right to reject any of the quotations or all the quotations without assigning any reason whatsoever.

Sd/-
REGISTRAR(i/c)

To,

1. Notice Board.
2. Website

KANNUR UNIVERSITY

QUOTATION SCHEDULE

Name of work: Rain water harvesting tank

Time of completion: One month

SL.NO.	QTY	PARTICULARS	UNIT	RATE	RATE IN WORDS	AMOUNT
1	20.088	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead up to 50 m and lift up to 1.5 m, disposed earth to be levelled and neatly dressed.All kinds of soil	cum			
2	1.089	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 nominal size)	cum			
3	2.971	Laterate masonry with neatly dressed laterate stone available reusable stone of size 40x20x15cm or nearest size in cement mortar 1:6 for foundation and basement including labour charges etc.	cum			
4	3.043	Supplying, filling, spreading & leveling stone boulders of size range 5 cm to 20 cm, in recharge pit, in the required thickness, for all leads & lifts, all complete as per direction of Engineer -in- charges	cum			
5	1.691	Supplying, filling, spreading & leveling gravels of size range 5 mm to 10 mm, in the recharge pit, over the existing layer of boulders, in required thickness, for all leads & lifts, all complete as per direction of Engineer -in-Charge	cum			
6	1.353	Supplying, filling, spreading & leveling coarse sand of size range 1.5 mm to 2 mm in recharge pit, in required thickness over gravel layer, for all leads & lifts, all complete as per direction of Engineer-in-charge.	cum			

KANNUR UNIVERSITY
QUOTATION SCHEDULE

Name of work: Rain water harvesting tank				Time of completion: One month		
SL.NO.	QTY	PARTICULARS	UNIT	RATE	RATE IN WORDS	AMOUNT
7	22.4	12 mm cement plaster of mix: 1:4 (1 cement : 4 fine sand)	sqm			
8	16	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete: 450 mm dia R.C.C. pipe	m			
		Total				

Signature of contractor

Registrar

Name & Address

Kannur University